

# **Right ELEVATION**

WESTERN TRUSS JOB # 2001565

JOB NAME : YAVAPAI COUNTY 1 BDRM

JOB SITE ADDRESS : YAVAPAI COUNTY

DATE : 10-2-20

1X

REVIEWED FOR DESIGN  
CRITERIA ONLY



**MiTek USA, Inc.**

MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661  
Telephone 916-755-3571

Re: 2001565  
YAVAPAI COUNTY 1 BDRM

The truss drawing(s) referenced below have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Western Truss.

Pages or sheets covered by this seal: R63988693 thru R63988710

My license renewal date for the state of Arizona is March 31, 2022.

Arizona COA: 11906-0

Lumber design values are in accordance with ANSI/TPI 1 section 6.3  
These truss designs rely on lumber values established by others.



October 8, 2020

Dyer, Cecil

**IMPORTANT NOTE:** The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

REVIEWED FOR  
DESIGN CRITERIA  
ONLY




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R6398693
2001565	A01	Hip Girder	2	2	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 06004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MITek Industries, Inc. Wed Oct 07 16:51:38  
ID:VGO1\_00jPDKKvhcmHlWYkml-m9Hv3u96Ch5F27bGCxy\_m3DF8XGEB1SjwCOLTyVI2L

Page: 1



Scale = 1/45

Plate Offsets (X, Y): [2:0-1-10,Edge], [3:0-6-0,0-3-8], [5:0-6-0,0-3-8], [6:0-1-10,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	Vert(LL)	-0.33	8-10	>825	240	MT20	169/123
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	Vert(CT)	-0.46	8-10	>586	180		
TCDL	15.0	Rep Stress Incr	NO	WB	Horz(CT)	0.10	6	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-SH							
BCDL	10.0										
										Weight: 209 lb	FT = 20%

#### LUMBER

TOP CHORD 2x6 SPF 1650F 1.5E  
BOT CHORD 2x6 SPF 1650F 1.5E  
WEBS 2x4 WW Stud/Std \*Except\* 8-3,8-5;2x4 SPF 1650F 1.5E

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 4-11-11 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 2=0-5-8, 6=0-5-8  
Max Horiz 2=66 (LC 6)  
Max Uplift 2=641 (LC 6), 6=529 (LC 7)  
Max Grav 2=3917 (LC 17), 6=3644 (LC 18)

#### FORCES

(lb) - Maximum Compression/Maximum Tension

#### TOP CHORD

1-2=0/101, 2-11=-9881/1371,  
3-11=-9698/1392, 3-4=-12595/1840,  
4-5=-12595/1840, 5-12=-9801/1447,  
6-12=-9990/1436

#### BOT CHORD

2-10=-1279/9204, 9-10=-1288/9306,  
9-13=-1288/9306, 13-14=-1288/9306,  
8-14=-1288/9306, 8-15=-1317/9420,  
15-16=-1317/9420, 7-16=-1317/9420,  
6-7=-1306/9315

#### WEBS

3-10=-136/1436, 3-8=-550/3535,  
4-8=-865/208, 5-8=-529/3485, 5-7=-146/1491

#### NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
Web connected as follows: 2x4 - 1 row at 0-2-0 oc, Except member 3-8 2x4 - 1 row at 0-9-0 oc, Except member 5-8 2x4 - 1 row at 0-9-0 oc, member 4-8 2x4 - 1 row at 0-4-0 oc.
- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; Lumber DOL=1.33 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with any other live loads.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 529 lb uplift at joint 6 and 641 lb uplift at joint 2.

- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 976 lb down and 162 lb up at 6-0-0, 429 lb down and 81 lb up at 8-0-12, 429 lb down and 81 lb up at 10-0-12, 429 lb down and 81 lb up at 11-6-0, 429 lb down and 81 lb up at 12-11-4, and 429 lb down and 81 lb up at 14-11-4, and 976 lb down and 162 lb up at 16-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

#### LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-3=-110, 3-5=-110, 5-6=-110, 2-6=-20  
Concentrated Loads (lb)  
Vert: 10=-976 (F), 8=-429 (F), 7=-976 (F), 13=-429 (F), 14=-429 (F), 15=-429 (F), 16=-429 (F)



REVIEWED FOR DESIGN CRITERIA ONLY  
October 8, 2020


**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MITek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Rossville, CA 95061





Scale = 1:45.3

Plate Offsets (X, Y): [2:0-0-2,Edge], [5:0-0-6,Edge], [7:0-3-0,0-3-4]

[illegible]

## LUMBER

TOP CHORD	2x6 SPF 1650F 1.5E
BOT CHORD	2x4 SPF 1650F 1.5E
WEBS	2x4 WW Stud/Std

## BRACING

**TOP CHORD** Structural wood sheathing directly applied or 2-7-9 oc purlins.

**BOT CHORD** Rigid ceiling directly applied or 10-0-0 oc  
bracing.

## REACTIONS

(size) 2=0-5-8, 5=0-5-8  
 Max Horiz 2=73 (LC 14)  
 Max Uplift 2=-307 (LC 10), 5=-195 (LC 11)  
 Max Grav 2=2044 (LC 35), 5=1638 (LC 35)

## FORCES

(lb) - Maximum Compression/Maximum Tension

**TOP CHORD**

1-2=0/89, 2-8=-3373/505, 8-9=-3345/518,  
9-10=-3239/520, 3-10=-3219/537,  
3-11=-3106/553, 11-12=-3106/553,  
12-13=-3106/553, 4-13=-3106/553,  
4-14=-3299/544, 14-15=-3307/527,  
5-15=-3413/526

**BOT CHORD**

2-7=-430/3029, 6-7=-425/3038,  
5-6=-429/3105

## WEBS

 $3-7=0/293, 3-6=-313/422, 4-6=0/292$ 

## NOTES

- 1) Wind: ASCE 7-16; Vult=15mph (3-second gust)  
Vasd=91mph; TCdL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; Hail Roof; Hail Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) 2-0-14 to 0-11-2, Interior (1) 0-11-2 to 8-0-0, Exterior(2R) 8-0-0 to 12-2-15, Interior (1) 12-2-15 to 19-5-0, Exterior(2R) 15-0-0 to 19-2-15, Interior (1) 19-2-15 to 22-9-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grp DOL=1.33
- 2) TLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1-0; Rough Cat C; Partially Exp.; Ce=1-0; Cs=1.00; Ct=1.10

- 3) Unbalanced snow loads have been considered for this design.
- 4) This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with other live loads.
- 5) Provide adequate drainage to prevent water ponding.
- 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 7) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 195 lb uplift at joint 5 and 307 lb uplift at joint 2.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



REVIEWED FOR  
DESIGN CRITERIA  
ONLY



**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.**

Design valid for use only with Mitek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, and building design, verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is for preventing buckling of members only. Additional bracing may be required for permanent bracing as always required for stability and to provide guidance with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCS1 Building Component Safety Information**, available from Truss Plate Institute, 2670 Grain Highway, Suite 203 Waldorf, MD 20601.



**MITek USA, Inc.**  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988695
2001565	A03	Hip	2	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:41  
ID:wLv6nxwFCT34VPGmLLIVFYkmO-775o6bDE1EKY9mUD7UX9T7w6XYwTsEC23U668vy7V2G

Page: 1



Scale = 1:45.5

Plate Offsets (X, Y): [2:0-1-2,Edge], [7:0-5-2,0-1-8], [9:0-4-0,0-3-4]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.44	Vert(LL)	-0.20	8-9	>999	240	169/123
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.99	Vert(CT)	-0.44	7-8	>608	180	
TCDL	15.0	Rep Stress Incr	NO	WB	0.78	Horz(CT)	0.13	7	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-SH							
BCDL	10.0										
Weight: 93 lb FT = 20%											

#### LUMBER

TOP CHORD 2x6 SPF 1650F 1.5E  
BOT CHORD 2x4 SPF 1650F 1.5E  
WEBS 2x4 WW Stud/Std

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 3-9-10 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 2=0-5-8, 7=0-5-8  
Max Horiz 2=86 (LC 14)  
Max Uplift 2=-178 (LC 10), 7=-65 (LC 11)  
Max Grav 2=2373 (LC 35), 7=1967 (LC 35)

#### FORCES

(lb) - Maximum Compression/Maximum Tension

#### TOP CHORD

1-10=0/19, 2-10=0/89, 2-11=-4364/263,  
11-12=-4298/264, 3-12=-4214/282,  
3-13=-3387/121, 13-14=-3263/127,  
4-14=-3131/173, 4-15=-3138/154,  
5-15=-3138/154, 5-16=-3161/169,  
16-17=-3288/132, 6-17=-3416/117,  
6-18=-4338/286, 18-19=-4386/276,  
7-19=-4478/267

#### BOT CHORD

2-9=-210/3949, 8-9=-12/3112, 7-8=-215/4110  
WEBS 4-9=0/429, 4-8=-236/284, 5-8=-26/481,  
3-9=-913/211, 6-8=-1059/240

#### NOTES

- Wind: ASCE 7-16; Vult=115mph (3-second gust)  
Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; Hip Roof; Hip Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) 2-0-14 to 0-11-2, Interior (1) 0-11-2 to 10-0-0, Exterior(2E) 10-0-0 to 13-0-0, Exterior(2R) 13-0-0 to 17-2-15, Interior (1) 17-2-15 to 22-9-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33

- TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 65 lb uplift at joint 7 and 178 lb uplift at joint 2.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Load case(s) 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.

#### LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-110, 4-5=-110, 5-7=-110, 2-7=-20  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- Dead + 0.75 Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)

Vert: 1-4=-90, 4-5=-90, 5-7=-90, 2-7=-20  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118

- Dead + 0.75 Snow (Unbal. Left): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-12=-90, 4-12=-113, 4-5=-113, 5-7=-48, 2-7=-20  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118

- Dead + 0.75 Snow (Unbal. Right): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-48, 4-5=-113, 5-19=-113, 7-19=-90, 2-7=-20  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118

- Dead + Uninhabitable Attic Without Storage: Lumber Increase=1.25, Plate Increase=1.25  
Uniform Loads (lb/ft)  
Vert: 1-4=-30, 4-5=-30, 5-7=-30, 2-7=-40



REVIEWED FOR  
DESIGN CRITERIA  
ONLY  
October 8, 2020

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSITPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661



Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988695
2001565	A03	Hip	2	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:41  
ID: wL6bnxwFCT34VPgmLlRVFYKmoD-775o6bDE1EkY9mUD7X9T7w6XYvTsEC23U686vYV2G

Page: 2

- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 6) Dead + 0.6 C-C Wind (Pos. Internal) Case 1: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=70, 2-11=42, 4-11=29, 4-5=42, 5-17=41, 7-17=29, 2-7=-12  
Horz: 1-2=-82, 2-11=-54, 4-11=-41, 5-17=53, 7-17=41
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 7) Dead + 0.6 C-C Wind (Pos. Internal) Case 2: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=23, 2-13=29, 4-13=41, 4-5=41, 5-18=29, 7-18=42, 2-7=-12  
Horz: 1-2=-35, 2-13=-41, 4-13=-53, 5-18=41, 7-18=54
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 8) Dead + 0.6 C-C Wind (Neg. Internal) Case 1: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-20, 2-4=-47, 4-5=-47, 5-7=-47, 2-7=-20  
Horz: 1-2=-10, 2-4=17, 5-7=-17
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 9) Dead + 0.6 C-C Wind (Neg. Internal) Case 2: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-40, 2-4=-47, 4-5=-47, 5-7=-47, 2-7=-20  
Horz: 1-2=10, 2-4=17, 5-7=-17
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 10) Dead + 0.6 MWFRS Wind (Pos. Internal) Left: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=46, 2-4=31, 4-5=31, 5-7=18, 2-7=-12  
Horz: 1-2=-58, 2-4=-43, 5-7=30
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 11) Dead + 0.6 MWFRS Wind (Pos. Internal) Right: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=11, 2-4=18, 4-5=31, 5-7=31, 2-7=-12  
Horz: 1-2=-23, 2-4=-30, 5-7=43
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 12) Dead + 0.6 MWFRS Wind (Neg. Internal) Left: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=7, 2-4=1, 4-5=1, 5-7=-13, 2-7=-20  
Horz: 1-2=-37, 2-4=-31, 5-7=17
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 13) Dead + 0.6 MWFRS Wind (Neg. Internal) Right: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-7, 2-4=-13, 4-5=1, 5-7=1, 2-7=-20  
Horz: 1-2=-23, 2-4=-17, 5-7=31
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 14) Dead + 0.6 MWFRS Wind (Pos. Internal) 1st Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=25, 2-4=31, 4-15=31, 5-15=13, 5-7=13, 2-7=-12  
Horz: 1-2=-37, 2-4=-43, 5-7=25
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 15) Dead + 0.6 MWFRS Wind (Pos. Internal) 2nd Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=6, 2-4=13, 4-15=13, 5-15=31, 5-7=31, 2-7=-12
- Horz: 1-2=-18, 2-4=-25, 5-7=43
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 16) Dead + 0.6 MWFRS Wind (Pos. Internal) 3rd Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=12, 2-4=18, 4-15=18, 5-15=7, 5-7=7, 2-7=-12  
Horz: 1-2=-24, 2-4=-30, 5-7=19
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 17) Dead + 0.6 MWFRS Wind (Pos. Internal) 4th Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=1, 2-4=7, 4-15=7, 5-15=18, 5-7=18, 2-7=-12  
Horz: 1-2=-13, 2-4=-19, 5-7=30
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 18) Dead + 0.6 MWFRS Wind (Neg. Internal) 1st Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=7, 2-4=1, 4-15=1, 5-15=-18, 5-7=-18, 2-7=-20  
Horz: 1-2=-37, 2-4=-31, 5-7=12
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 19) Dead + 0.6 MWFRS Wind (Neg. Internal) 2nd Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-12, 2-4=-18, 4-15=-18, 5-15=1, 5-7=1, 2-7=-20  
Horz: 1-2=-18, 2-4=-12, 5-7=31
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 20) Dead + Snow on Overhangs: Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-2=-110, 2-4=-30, 4-5=-30, 5-7=-30, 2-7=-20
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 21) Dead + Snow (Unbal. Left): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-12=-110, 4-12=-140, 4-5=-140, 5-7=-54, 2-7=-20
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 22) Dead + Snow (Unbal. Right): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-54, 4-5=-140, 5-19=-140, 7-19=-110, 2-7=-20
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 23) Dead: Lumber Increase=0.90, Plate Increase=0.90 Pl. metal=0.90  
Uniform Loads (lb/ft)  
Vert: 1-4=-30, 4-5=-30, 5-7=-30, 2-7=-20
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 24) Dead + 0.75 Snow (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) Left): Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-62, 2-4=-67, 4-5=-67, 5-7=-77, 2-7=-20  
Horz: 1-2=-28, 2-4=-23, 5-7=13
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 25) Dead + 0.75 Snow (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) Right): Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-73, 2-4=-77, 4-5=-67, 5-7=-67, 2-7=-20  
Horz: 1-2=-17, 2-4=-13, 5-7=23
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 26) Dead + 0.75 Snow (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) 1st Parallel): Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-62, 2-4=-67, 4-15=-67, 5-15=-81, 5-7=-81, 2-7=-20  
Horz: 1-2=-28, 2-4=-23, 5-7=9
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 27) Dead + 0.75 Snow (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) 2nd Parallel): Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-76, 2-4=-81, 4-15=-81, 5-15=-67, 5-7=-67, 2-7=-20  
Horz: 1-2=-14, 2-4=-9, 5-7=23
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 28) Dead + 0.6 C-C Wind Min. Down: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=4, 2-4=-28, 4-5=-28, 5-7=-28, 2-7=-12  
Horz: 1-2=-16, 2-4=16, 5-7=-16
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 29) Dead + 0.6 C-C Wind Min. Upward: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-4=4, 4-5=4, 5-7=4, 2-7=-12  
Horz: 1-4=-16, 5-7=16
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 30) 3rd Dead + 0.75 Snow (Unbal. Left): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-48, 4-5=-113, 5-7=-48, 2-7=-20
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 31) 4th Dead + 0.75 Snow (Unbal. Left): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-10=-90, 4-10=-113, 4-5=-48, 5-7=-48, 2-7=-20
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 32) 5th Dead + 0.75 Snow (Unbal. Right): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-48, 4-5=-113, 5-7=-48, 2-7=-20
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 33) 6th Dead + 0.75 Snow (Unbal. Right): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-48, 4-5=-48, 5-7=-113, 2-7=-20
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 34) 7th Unbal. Dead + Snow (balanced) + Parallel: Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-54, 4-5=-160, 5-7=-54, 2-7=-20
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 35) 8th Unbal. Dead + Snow (balanced) + Parallel: Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-160, 4-5=-54, 5-7=-160, 2-7=-20
- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 36) 9th Unbal. Dead + Snow (Unbal. Left) + Parallel: Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-2=-73, 2-4=-77, 4-5=-67, 5-7=-67, 2-7=-20

DESIGN CRITERIA ONLY

Continued on page 3

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MI-7473 rev. 6/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSIPR Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Rossville, CA 95061



Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988695
2001565	A03	Hip	2	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:41  
ID: wLV6nxwFCT34VPGmLLtVfyYkmO-775o6bDE1EkY9mUD7UX9T7w6XYvTsEC23U668vyVIG2

Page: 3

- Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 37) 10th Unbal.Death + Snow (Unbal. Left) + Parallel:  
Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-10=-110, 4-10=-140, 4-5=-54, 5-7=-54,  
2-7=-20  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 38) 11th Unbal.Death + Snow (Unbal. Right) + Parallel:  
Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-54, 4-5=-140, 5-7=-54, 2-7=-20  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 39) 12th Unbal.Death + Snow (Unbal. Right) + Parallel:  
Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-54, 4-5=-54, 5-7=-140, 2-7=-20  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 40) 13th Unbal.Death + 0.75 Snow (balanced) + Parallel:  
Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-48, 4-5=-127, 5-7=-48, 2-7=-20  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 41) 14th Unbal.Death + 0.75 Snow (balanced) + Parallel:  
Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-4=-127, 4-5=-48, 5-7=-127, 2-7=-20  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 42) 15th Unbal.Death + 0.75 Snow (unbal.) + 0.75(0.6  
MWFRS Wind (Neg. Int) Left) + Parallel: Lumber  
Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-20, 2-4=-25, 4-5=-104, 5-7=-35, 2-7=-20  
Horz: 1-2=-28, 2-4=-23, 5-7=13  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 43) 16th Unbal.Death + 0.75 Snow (unbal.) + 0.75(0.6  
MWFRS Wind (Neg. Int) Left) + Parallel: Lumber  
Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-100, 2-4=-104, 4-5=-25, 5-7=-115,  
2-7=-20  
Horz: 1-2=-28, 2-4=-23, 5-7=13  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 44) 17th Unbal.Death + 0.75 Snow (unbal.) + 0.75(0.6  
MWFRS Wind (Neg. Int) Right) + Parallel: Lumber  
Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-31, 2-4=-35, 4-5=-104, 5-7=-25, 2-7=-20  
Horz: 1-2=-17, 2-4=-13, 5-7=23  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 45) 18th Unbal.Death + 0.75 Snow (unbal.) + 0.75(0.6  
MWFRS Wind (Neg. Int) Right) + Parallel: Lumber  
Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-110, 2-4=-115, 4-5=-25, 5-7=-104, 2-7=-20  
Horz: 1-2=-17, 2-4=-13, 5-7=23  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 46) 19th Unbal.Death + 0.75 Snow (unbal.) + 0.75(0.6  
MWFRS Wind (Neg. Int) 1st Parallel): Lumber  
Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-20, 2-4=-25, 4-15=-104, 5-15=-118,  
5-7=-39, 2-7=-20  
Horz: 1-2=-28, 2-4=-23, 5-7=9  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 47) 20th Unbal.Death + 0.75 Snow (unbal.) + 0.75(0.6  
MWFRS Wind (Neg. Int) 1st Parallel): Lumber  
Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-100, 2-4=-104, 4-15=-25, 5-15=-39,  
5-7=-118, 2-7=-20  
Horz: 1-2=-28, 2-4=-23, 5-7=9  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 48) 21st Unbal.Death + 0.75 Snow (unbal.) + 0.75(0.6  
MWFRS Wind (Neg. Int) 2nd Parallel): Lumber  
Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-34, 2-4=-39, 4-15=-118, 5-15=-104,  
5-7=-25, 2-7=-20  
Horz: 1-2=-14, 2-4=-9, 5-7=23  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118
- 49) 22nd Unbal.Death + 0.75 Snow (unbal.) + 0.75(0.6  
MWFRS Wind (Neg. Int) 2nd Parallel): Lumber  
Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-114, 2-4=-118, 4-15=-39, 5-15=-25,  
5-7=-104, 2-7=-20  
Horz: 1-2=-14, 2-4=-9, 5-7=23  
Concentrated Loads (lb)  
Vert: 14=-117, 16=-118

REVIEWED FOR  
DESIGN CRITERIA  
ONLY

**WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MI-7473 rev. 5/19/2020 BEFORE USE.**  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
MITek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Rosville, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988696
2001565	A04	Common	3	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:43  
ID:OXTV\_HxlzmBx6Zryu3A62TyYkmN-3WCZXHEVZr\_GO4ec6vadZY?R7MehK5LLXobCcoyV12E

Page: 1



Scale = 1:45.6

Plate Offsets (X, Y): [2:0-5-2,0-1-8], [5:0-3-0,Edge], [8:0-5-2,0-1-8], [10:0-3-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.43	Ver(LL)	-0.21	8-9	>999	240	197/144
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.81	Ver(CT)	-0.33	8-9	>808	180	
TCDL	15.0	Rep Stress Incr	NO	WB	0.99	Horz(CT)	0.11	8	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-SH							
BCDL	10.0										
Weight: 89 lb FT = 20%											

#### LUMBER

TOP CHORD 2x6 SPF 1650F 1.5E

BOT CHORD 2x4 SPF 1650F 1.5E

WEBS 2x4 WW Stud/Std

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 4-1-11 oc purlins.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 2=0-5-8, 8=0-5-8

Max Horiz 2=95 (LC 14)

Max Uplift 2=-167 (LC 10), 8=-55 (LC 11)

Max Grav 2=1929 (LC 21), 8=1656 (LC 22)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/61, 2-11=-3764/165, 11-12=-3649/165,

3-12=-3648/186, 3-13=-3181/118,

4-13=-3070/129, 4-5=-896/88, 5-6=-887/98,

6-14=-3110/150, 7-14=-3254/138,

7-15=-3757/210, 8-15=-3851/197

BOT CHORD 2-10=-119/3426, 9-10=0/2681,

8-9=-132/3546

WEBS 7-9=-901/233, 3-10=-811/210, 4-10=-67/801,

4-6=-1814/62, 6-9=-89/886

#### NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; Hip Roof; Common Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) 2-0-14 to 0-11-2, Interior (1) 0-11-2 to 11-6-0, Exterior(2R) 11-6-0 to 15-8-15, Interior (1) 15-8-15 to 22-9-4 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10

- 3) Unbalanced snow loads have been considered for this design.
- 4) This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 55 lb uplift at joint 8 and 167 lb uplift at joint 2.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 9) Load case(s) 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29 has/have been modified. Building designer must review loads to verify that they are correct for the intended use of this truss.
- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 118 lb down at 13-6-0, and 118 lb down at 9-6-0 on top chord. The design/selection of such connection device (s) is the responsibility of others.
- 11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-5=-110, 5-8=-110, 2-8=-20  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)

- 2) Dead + 0.75 Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-5=-90, 5-8=-90, 2-8=-20  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 3) Dead + 0.75 Snow (Unbal. Left): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-12=-90, 5-12=-122, 5-8=-48, 2-8=-20  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 4) Dead + 0.75 Snow (Unbal. Right): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-5=-48, 5-15=-122, 8-15=-90, 2-8=-20  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 5) Dead + Uninhabitable Attic Without Storage: Lumber Increase=1.25, Plate Increase=1.25  
Uniform Loads (lb/ft)



REVIEWED FOR DESIGN CRITERIA ONLY  
October 8, 2020

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661



Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	
2001565	A04	Common	3	1	Job Reference (optional)	R63988696

Western Truss & Components, Flagstaff, AZ - 06004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MITek Industries, Inc. Wed Oct 07 16:51:43  
ID:OKTV\_HxzmBx6Zryu3A62TyYkmN-3WCZXHEVZr\_GO4ec6vadZY7R7MehK5LLXobCCoyV12E

Page: 2

- Vert: 1-5=-30, 5-8=-30, 2-8=-40  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 6) Dead + 0.6 C-C Wind (Pos. Internal) Case 1: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=70, 2-11=42, 5-11=29, 5-14=41, 8-14=29, 2-8=-12  
Horz: 1-2=-82, 2-11=-54, 5-11=-41, 5-14=53, 8-14=41  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 7) Dead + 0.6 C-C Wind (Pos. Internal) Case 2: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=23, 2-13=29, 5-13=41, 5-15=29, 8-15=42, 2-8=-12  
Horz: 1-2=-35, 2-13=-41, 5-13=-53, 5-15=41, 8-15=54  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 8) Dead + 0.6 C-C Wind (Neg. Internal) Case 1: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-20, 2-5=-47, 5-8=-47, 2-8=-20  
Horz: 1-2=-10, 2-5=17, 5-8=-17  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 9) Dead + 0.6 C-C Wind (Neg. Internal) Case 2: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-40, 2-5=-47, 5-8=-47, 2-8=-20  
Horz: 1-2=10, 2-5=17, 5-8=-17  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 10) Dead + 0.6 MWFRS Wind (Pos. Internal) Left: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=46, 2-5=31, 5-8=18, 2-8=-12  
Horz: 1-2=-58, 2-5=-43, 5-8=30  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 11) Dead + 0.6 MWFRS Wind (Pos. Internal) Right: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=11, 2-5=18, 5-8=31, 2-8=-12  
Horz: 1-2=-23, 2-5=-30, 5-8=43  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 12) Dead + 0.6 MWFRS Wind (Neg. Internal) Left: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=7, 2-5=1, 5-8=-13, 2-8=-20  
Horz: 1-2=-37, 2-5=-31, 5-8=17  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 13) Dead + 0.6 MWFRS Wind (Neg. Internal) Right: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-7, 2-5=-13, 5-8=1, 2-8=-20  
Horz: 1-2=-23, 2-5=-17, 5-8=31  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 14) Dead + 0.6 MWFRS Wind (Pos. Internal) 1st Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=25, 2-5=31, 5-8=13, 2-8=-12  
Horz: 1-2=-37, 2-5=-43, 5-8=25  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 15) Dead + 0.6 MWFRS Wind (Pos. Internal) 2nd Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=6, 2-5=13, 5-8=31, 2-8=-12  
Horz: 1-2=-18, 2-5=-25, 5-8=43
- Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 16) Dead + 0.6 MWFRS Wind (Pos. Internal) 3rd Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=12, 2-5=18, 5-8=7, 2-8=-12  
Horz: 1-2=-24, 2-5=-30, 5-8=19  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 17) Dead + 0.6 MWFRS Wind (Pos. Internal) 4th Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=1, 2-5=7, 5-8=18, 2-8=-12  
Horz: 1-2=-13, 2-5=-19, 5-8=30  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 18) Dead + 0.6 MWFRS Wind (Neg. Internal) 1st Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=7, 2-5=1, 5-8=-18, 2-8=-20  
Horz: 1-2=-37, 2-5=-31, 5-8=12  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 19) Dead + 0.6 MWFRS Wind (Neg. Internal) 2nd Parallel: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-12, 2-5=-18, 5-8=1, 2-8=-20  
Horz: 1-2=-18, 2-5=-12, 5-8=31  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 20) Dead + Snow on Overhangs: Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-2=-110, 2-5=-30, 5-8=-30, 2-8=-20  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 21) Dead + Snow (Unbal. Left): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-12=-110, 5-12=-153, 5-8=-54, 2-8=-20  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 22) Dead + Snow (Unbal. Right): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-5=-54, 5-15=-153, 8-15=-110, 2-8=-20  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 23) Dead: Lumber Increase=0.90, Plate Increase=0.90 Pli. metal=0.90  
Uniform Loads (lb/ft)  
Vert: 1-5=-30, 5-8=-30, 2-8=-20  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 24) Dead + 0.75 Snow (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) Left): Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-62, 2-5=-67, 5-8=-77, 2-8=-20  
Horz: 1-2=-28, 2-5=-23, 5-8=13  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 25) Dead + 0.75 Snow (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) Right): Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-73, 2-5=-77, 5-8=-67, 2-8=-20  
Horz: 1-2=-17, 2-5=-13, 5-8=23  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 26) Dead + 0.75 Snow (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) 1st Parallel): Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-62, 2-5=-67, 5-8=-81, 2-8=-20
- Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- Horz: 1-2=-28, 2-5=-23, 5-8=9  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 27) Dead + 0.75 Snow (bal.) + 0.75(0.6 MWFRS Wind (Neg. Int) 2nd Parallel): Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=-76, 2-5=-81, 5-8=-67, 2-8=-20  
Horz: 1-2=-14, 2-5=-9, 5-8=23  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 28) Dead + 0.6 C-C Wind Min. Down: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-2=4, 2-5=-28, 5-8=-28, 2-8=-12  
Horz: 1-2=-16, 2-5=16, 5-8=-16  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)
- 29) Dead + 0.6 C-C Wind Min. Upward: Lumber Increase=1.33, Plate Increase=1.33  
Uniform Loads (lb/ft)  
Vert: 1-5=4, 5-8=4, 2-8=-12  
Horz: 1-5=-16, 5-8=16  
Concentrated Loads (lb)  
Vert: 4=-118 (F), 6=-118 (F)

REVIEWED FOR  
DESIGN CRITERIA  
ONLY

**WARNING -** Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based on parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANS/TFII Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MITek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988697
2001565	B01	Hip Girder	1	2	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:44  
ID:h108sg0GKw3xSelp1olqxyYkmG-XlmkdF7K9670DDogc5s5iYHm2y3cgVmSKmlEyI2D

Page: 1



Scale = 1/43.8

Plate Offsets (X, Y): [9:0-4-0,0-4-8]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	-0.19	8-9	>999	240	169/123
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.55	Vert(CT)	-0.27	8-9	>881	180	
TCDL	15.0	Rep Stress Incr	NO	WB	0.73	Horz(CT)	0.07	6	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Malrix-SH							
BCDL	10.0										
Weight: 186 lb FT = 20%											

#### LUMBER

TOP CHORD 2x6 SPF 1650F 1.5E  
BOT CHORD 2x6 SPF 1650F 1.5E  
WEBS 2x4 WW Stud/Std

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 2=0-5-8, 6=0-5-8  
Max Horiz 2=51 (LC 46)  
Max Uplift 2=537 (LC 6), 6=537 (LC 7)  
Max Grav 2=3321 (LC 31), 6=3321 (LC 31)

#### FORCES

(lb) - Maximum Compression/Maximum Tension

#### TOP CHORD

1-2=0/101, 2-11=7908/1048,  
3-11=7776/1069, 3-4=8738/1253,  
4-5=8738/1253, 5-12=7776/1070,  
6-12=7907/1049, 6-7=0/101

#### BOT CHORD

2-10=958/7332, 10-13=966/7421,  
9-13=966/7421, 9-14=934/7421,  
8-14=934/7421, 6-8=927/7332

#### WEBS

3-10=111/1246, 3-9=271/1763,  
4-9=575/146, 5-9=273/1763, 5-8=110/1246

#### NOTES

- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:  
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.  
Web connected as follows: 2x4 - 1 row at 0-2-0 oc, Except member 3-9 2x4 - 1 row at 0-9-0 oc, Except member 5-9 2x4 - 1 row at 0-9-0 oc, member 4-9 2x4 - 1 row at 0-4-0 oc.

- All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
- Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; Lumber DOL=1.33 plate grip DOL=1.33
- TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- Unbalanced snow loads have been considered for this design.
- This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with other live loads.
- Provide adequate drainage to prevent water ponding.
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 537 lb uplift at joint 2 and 537 lb uplift at joint 6.
- This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 976 lb down and 162 lb up at 6-0-0, 429 lb down and 81 lb up at 8-0-12, 429 lb down and 81 lb up at 10-0-0, and 429 lb down and 81 lb up at 11-11-4, and 976 lb down and 162 lb up at 13-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

#### LOAD CASE(S) Standard

- Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-3=-110, 3-5=-110, 5-7=-110, 2-6=-20  
Concentrated Loads (lb)  
Vert: 10=-976 (F), 9=-429 (F), 8=-976 (F), 13=-429 (F), 14=-429 (F)



REVIEWED FOR  
DESIGN CRITERIA  
ONLY  
October 8, 2020

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R6398698
2001565	B02	Hip	1	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 0.33 S Jul 22 2020 Print: 0.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:44  
ID: OXTV\_HxlzmBx6Zryu3A62TyYkmN-XimxkdF7K9670DDogc5s5iYYCm1v3jyVmSkmlEyVi2D

Page: 1



Scale = 1/43.9

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.67	Vert(LL)	-0.14	2-9	>999	240	169/123
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.62	Vert(CT)	-0.27	2-9	>868	180	
TCDL	15.0	Rep Stress Incr	YES	WB	0.26	Horz(CT)	0.07	5	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-SH							
BCDL	10.0										
										Weight: 77 lb	FT = 20%

#### LUMBER

TOP CHORD 2x6 SPF 1650F 1.5E  
BOT CHORD 2x4 SPF 1650F 1.5E  
WEBS 2x4 WW Stud/Std

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 3-10-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 2=0-5-8, 5=0-5-8  
Max Horiz 2=-63 (LC 19)  
Max Uplift 2=-274 (LC 10), 5=-274 (LC 11)  
Max Grav 2=1914 (LC 35), 5=1914 (LC 35)

#### FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/89, 2-10=-2709/434, 10-11=-2672/448,  
3-11=-2493/466, 3-12=-2356/495,  
4-12=-2356/495, 4-13=-2496/472,  
13-14=-2675/455, 5-14=-2713/440, 5-6=0/89

#### BOT CHORD

2-9=-329/2346, 8-9=-326/2353,  
7-8=-326/2353, 5-7=-343/2349

#### WEBS

3-9=0/228, 3-7=-312/320, 4-7=-45/293

#### NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)  
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat.  
II; Exp C; Enclosed; Hip Roof; Hip Truss; MWFRS  
(envelope) exterior zone and C-C Exterior(2E) 2-0-14 to  
0-11-2, Interior (1) 0-11-2 to 8-0-0, Exterior(2E) 8-0-0 to  
12-0-0, Exterior(2R) 12-0-0 to 16-2-15, Interior (1)  
16-2-15 to 22-0-14 zone; C-C for members and forces &  
MWFRS for reactions shown; Lumber DOL=1.33 plate  
grip DOL=1.33
- 2) TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate  
DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0;  
Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this  
design.

- 4) This truss has been designed for greater of min roof live  
load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on  
overhangs non-concurrent with other live loads.
- 5) Provide adequate drainage to prevent water ponding.
- 6) This truss has been designed for a 10.0 psf bottom  
chord live load nonconcurrent with any other live loads.
- 7) \* This truss has been designed for a live load of 40.0psf  
on the bottom chord in all areas where a rectangle  
3-06-00 tall by 2-00-00 wide will fit between the bottom  
chord and any other members.
- 8) Provide mechanical connection (by others) of truss to  
bearing plate capable of withstanding 274 lb uplift at  
joint 2 and 274 lb uplift at joint 5.
- 9) This truss is designed in accordance with the 2018  
International Residential Code sections R502.11.1 and  
R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



REVIEWED FOR  
DESIGN CRITERIA  
ONLY

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MI-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Rossville, CA 95061




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988699
2001565	B03	Common	1	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 06004,

Run: 0.33 S Jul 22 2020 Print: 0.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:45  
ID:sk1(CdxWk4Jok)Q8SmhLbgYkmM-7uKJyyG15SE\_eNn\_EKc5ez5gx9Lmo9Ke\_64JHhyV12C

Page: 1



Scale = 1/4\"

Plate Offsets (X, Y): [6:0-4-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.15	TC	0.86	Vert(LL)	-0.25	2-6	>947	240	MT20	169/123
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.71	Vert(CT)	-0.43	2-6	>540	180		
TCDL	15.0	Rep Stress Incr	YES	WB	0.32	Horz(CT)	0.06	4	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-SH								
BCDL	10.0											
Weight: 72 lb											FT = 20%	

#### LUMBER

TOP CHORD 2x6 SPF 2100F 1.8E  
BOT CHORD 2x4 SPF 1650F 1.5E  
WEBS 2x4 WW Stud/Std

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 2=0-5-8, 4=0-5-8  
Max Horiz 2=-75 (LC 15)  
Max Uplift 2=-260 (LC 10), 4=-260 (LC 11)  
Max Grav 2=1642 (LC 21), 4=1642 (LC 22)

#### FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/61, 2-7=-2247/308, 7-8=-2211/312, 8-9=-2078/329, 3-9=-2045/347, 3-10=-2045/347, 10-11=-2078/329, 11-12=-2211/312, 4-12=-2247/308, 4-5=0/61  
BOT CHORD 2-6=-191/1959, 4-6=-191/1959  
WEBS 3-6=0/421

#### NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; Hip Roof; Common Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) -2-0-14 to 0-11-2, Interior (1) 0-11-2 to 10-0-0, Exterior(2R) 10-0-0 to 14-2-15, Interior (1) 14-2-15 to 22-0-14 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this design.

- 4) This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 260 lb uplift at joint 2 and 260 lb uplift at joint 4.
- 8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



REVIEWED FOR  
DESIGN CRITERIA  
ONLY

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Rossville, CA 95061




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988700
2001565	J01	Diagonal Hip Girder	6	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 06004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MITek Industries, Inc. Wed Oct 07 16:51:45  
ID:LwbFPzy8VORIM?LOUCa7uyYkml-7uKJyGISE\_eNn\_EKc5ez5i9SNoEKe\_64JHhyV2C

Page: 1



Scale = 1:24.9

Plate Offsets (X, Y): [2:0-5-5,0-0-2]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.56	Vert(LL)	-0.07	2-6	>999	240	169/123
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.29	Vert(CT)	-0.14	2-6	>669	180	
TCDL	15.0	Rep Stress Incr	NO	WB	0.00	Horz(CT)	0.00	5	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-P							
BCDL	10.0										
										Weight: 37 lb	FT = 20%

#### LUMBER

TOP CHORD 2x6 SPF 1650F 1.5E  
BOT CHORD 2x6 SPF 1650F 1.5E  
WEBS 2x4 WW Stud/Std

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 2=0-7-6, 5= Mechanical  
Max Horiz 2=105 (LC 36)  
Max Uplift 2=-217 (LC 6), 5=-53 (LC 7)  
Max Grav 2=1073 (LC 17), 5=575 (LC 17)

#### FORCES

(lb) - Maximum Compression/Maximum Tension  
TOP CHORD 1-7=0/34, 2-7=0/80, 2-8=-137/31, 8-9=-115/7,  
3-9=-59/82, 3-4=-11/0, 3-6=-499/112  
BOT CHORD 2-10=-29/22, 10-11=-29/22, 6-11=-29/22,  
5-6=0/0

#### NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)  
Vasd=91mph; TCCL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.33 plate grip DOL=1.33
- 2) TCCL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this design.
- 4) This truss has been designed for greater of min roof live load of 20.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- 6) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3'-06-00 tall by 2'-00-00 wide will fit between the bottom chord and any other members.
- 7) Refer to girder(s) for truss to truss connections.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 217 lb uplift at joint 2 and 53 lb uplift at joint 5.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 97 lb down and 302 lb up at 2-9-8, 97 lb down and 302 lb up at 2-9-8, and 109 lb down and 56 lb up at 5-7-7, and 109 lb down and 56 lb up at 5-7-7 on top chord, and 0 lb down at 2-9-8, 7 lb down at 2-9-8, and 20 lb down at 5-7-7, and 20 lb down at 5-7-7 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

#### LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15  
Uniform Loads (lb/ft)  
Vert: 1-3=-110, 3-4=-110, 2-5=-20  
Concentrated Loads (lb)  
Vert: 8=124 (F=62, B=62), 9=-59 (F=-30, B=-30),  
11=-18 (F=-9, B=-9)



REVIEWED FOR  
DESIGN CRITERIA  
ONLY  
October 8, 2020



**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSITPI® Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MITek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Rosville, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988701
2001565	J02	Jack-Closed	19	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MITek Industries, Inc. Wed Oct 07 16:51:46  
ID:sk11CdxWk4JokjQ8SmhLbgYkmM-T4uh9IHnrmMrFXMBn17KAAAd\_8Zp8XhaoDmPlp7yY12B

Page: 1



Scale = 1:23.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.26	Vert(LL)	-0.05	2-6	>999	240	MT20	169/123
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.25	Vert(CT)	-0.10	2-6	>648	180		
TCDL	15.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	n/a	-	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-P								
BCDL	10.0											
											Weight: 24 lb	FT = 20%

#### LUMBER

TOP CHORD 2x6 SPF 1650F 1.5E  
BOT CHORD 2x4 SPF 1650F 1.5E  
WEBS 2x4 WW Stud/Std

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 2=0-5-8, 6= Mechanical  
Max Horiz 2=124 (LC 10)  
Max Uplift 2=-164 (LC 10), 6=-61 (LC 14)  
Max Grav 2=898 (LC 21), 6=449 (LC 21)

#### FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=0/85, 2-7=-170/10, 7-8=-97/18,  
3-8=-90/91, 3-4=-13/0, 3-6=-388/231  
BOT CHORD 2-6=0/0, 5-6=0/0

#### NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)  
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cal. II; Exp C; Enclosed; Hip Roof; End Jack Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) -2-0-14 to 0-11-2, Interior (1) 0-11-2 to 6-0-0 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this design.
- 4) This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- 6) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 7) Refer to girder(s) for truss to truss connections.
  - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 61 lb uplift at joint 6 and 164 lb uplift at joint 2.
  - 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S) Standard



REVIEWED FOR  
DESIGN CRITERIA  
ONLY  
October 8, 2020

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.  
Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MITek**  
MITek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988702
2001565	J03L	Jack-Open	6	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:46  
ID:sk1ICdxWk4JokjQ8SmhLbgyYkmM-T4uh9IHnrmMrFXMBn17KAAd7PZrLXhaoDmPlp7yVi2B

Page: 1



Scale = 1:21

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.24	Vert(LL)	-0.01	2-4	>999	240	197/144
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.11	Vert(CT)	-0.02	2-4	>999	180	
TCDL	15.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-P							
BCDL	10.0										
										Weight: 16 lb	FT = 20%

#### LUMBER

TOP CHORD 2x6 SPF 1650F 1.5E  
BOT CHORD 2x4 SPF 1650F 1.5E

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 4-0-7 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 2=0-5-8, 3= Mechanical, 4= Mechanical  
Max Horiz 2=95 (LC 10)  
Max Uplift 2=-164 (LC 10), 3=-51 (LC 14)  
Max Grav 2=782 (LC 21), 3=178 (LC 21), 4=75 (LC 5)

#### FORCES

(lb) - Maximum Compression/Maximum Tension  
TOP CHORD 1-2=0/85, 2-5=-141/10, 3-5=-103/43  
BOT CHORD 2-4=0/0

#### NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)  
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; Hip Roof; End Jack Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) -2-0-14 to 0-11-2, Interior (1) 0-11-2 to 3-11-11 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this design.
- 4) This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- 6) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 7) Refer to girder(s) for truss to truss connections.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 3 and 164 lb uplift at joint 2.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



REVIEWED FOR DESIGN CRITERIA ONLY  
October 8, 2020

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988703
2001565	J03R	Jack-Open	6	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MITek Industries, Inc. Wed Oct 07 16:51:46  
ID:sk1tCdxWk4JokjQ8SmhLbgyYkmM-T4uh9IHnrmMrFXMBn17KAAd7PZrLXhaoDmnp7yVi2B

Page: 1



Scale = 1:21

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.24	Vert(LL)	-0.01	2-4	>999	240	MT20
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.11	Vert(CT)	-0.02	2-4	>999	180	197/144
TCDL	15.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-P							
BCDL	10.0										
										Weight: 16 lb	FT = 20%

**LUMBER**  
TOP CHORD 2x6 SPF 1650F 1.5E  
BOT CHORD 2x4 SPF 1650F 1.5E

**BRACING**  
TOP CHORD Structural wood sheathing directly applied or 4-0-7 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

**REACTIONS** (size) 2=0-5-8, 3= Mechanical, 4= Mechanical  
Max Horiz 2=95 (LC 10)  
Max Uplift 2=-164 (LC 10), 3=-51 (LC 14)  
Max Grav 2=782 (LC 21), 3=178 (LC 21), 4=75 (LC 5)

**FORCES** (lb) - Maximum Compression/Maximum Tension  
TOP CHORD 1-2=0/85, 2-5=-141/10, 3-5=-103/43  
BOT CHORD 2-4=0/0

- 6) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 7) Refer to girder(s) for truss to truss connections.
- 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 3 and 164 lb uplift at joint 2.
- 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard

#### NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust)  
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; Hip Roof; End Jack Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) -2-0-14 to 0-11-2, Interior (1) 0-11-2 to 3-11-11 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this design.
- 4) This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.



REVIEWED FOR DESIGN CRITERIA ONLY  
October 8, 2020

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.  
Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MITek**  
MITek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Rossville, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988704
2001565	J04L	Jack-Open	6	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:46  
ID:LwbFPzy8VORIMi7L0UCa7uyYkML-T4uh9IHnrmMrFXMBn17KAAd7WZskXhaoDmplt7yV12B

Page: 1



Scale = 1:19.7

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	0.00	2-4	>999	240	MT20
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	2-4	>999	180	197/144
TCDL	15.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-P							
BCDL	10.0										
Weight: 10 lb FT = 20%											

**LUMBER**  
TOP CHORD 2x6 SPF 1650F 1.5E  
BOT CHORD 2x4 SPF 1650F 1.5E  
**BRACING**  
TOP CHORD Structural wood sheathing directly applied or 2-0-7 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
**REACTIONS** (size) 2=0-5-8, 3= Mechanical, 4= Mechanical  
Max Horiz 2=67 (LC 10)  
Max Uplift 2=-189 (LC 10), 3=-141 (LC 20)  
Max Grav 2=713 (LC 21), 3=40 (LC 10), 4=35 (LC 5)

**FORCES** (lb) - Maximum Compression/Maximum Tension  
TOP CHORD 1-2=0/83, 2-5=-144/26, 3-5=-102/33  
BOT CHORD 2-4=0/0

#### NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; Hip Roof; End Jack Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) -2-0-14 to 0-11-2, Interior (1) 0-11-2 to 1-11-11 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) TCLL: ASCE 7-16; P=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Cl=1.10
- 3) Unbalanced snow loads have been considered for this design.
- 4) This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- 6) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 7) Refer to girder(s) for truss to truss connections.
  - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 141 lb uplift at joint 3 and 189 lb uplift at joint 2.
  - 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard



REVIEWED FOR DESIGN CRITERIA ONLY  
October 8, 2020

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 6/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988705
2001565	J04R	Jack-Open	6	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 0.33 S Jul 22 2020 Print: 0.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:47  
ID:LwbFPzy8VORfMI7L0UCa7uyYkml-xHS3MeI7c4UJlthxNLleZjOAAfZCzG8pxSQZQMZYVI2A

Page: 1



Scale = 1:19.7

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.23	Vert(LL)	0.00	2-4	>999	240	197/144
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.02	Vert(CT)	0.00	2-4	>999	180	
TCDL	15.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	3	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-P							
BCDL	10.0										
										Weight: 10 lb	FT = 20%

**LUMBER**  
TOP CHORD 2x6 SPF 1650F 1.5E  
BOT CHORD 2x4 SPF 1650F 1.5E  
**BRACING**  
TOP CHORD Structural wood sheathing directly applied or 2-0-7 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.  
**REACTIONS** (size) 2=0-5-8, 3= Mechanical, 4= Mechanical  
Max Horiz 2=67 (LC 10)  
Max Uplift 2=-189 (LC 10), 3=-141 (LC 20)  
Max Grav 2=713 (LC 21), 3=40 (LC 10), 4=35 (LC 5)

**FORCES** (lb) - Maximum Compression/Maximum Tension  
TOP CHORD 1-2=0/83, 2-5=-144/26, 3-5=-102/33  
BOT CHORD 2-4=0/0

#### NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; Hip Roof; End Jack Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) -2-0-14 to 0-11-2, Interior (1) 0-11-2 to 1-11-11 zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- 3) Unbalanced snow loads have been considered for this design.
- 4) This truss has been designed for greater of min roof live load of 16.0 psf or 1.00 times flat roof load of 40.0 psf on overhangs non-concurrent with other live loads.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.

- 6) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
  - 7) Refer to girder(s) for truss to truss connections.
  - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 141 lb uplift at joint 3 and 189 lb uplift at joint 2.
  - 9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- LOAD CASE(S)** Standard



REVIEWED FOR DESIGN CRITERIA ONLY  
October 8, 2020

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.  
Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANS/TP11 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

**MiTek**  
MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Rosedale, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988706
2001565	V01	Valley	1	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MITek Industries, Inc. Wed Oct 07 16:51:47  
ID:K3C3BCCQrjNVISl8vAyPyWSZN-xHS3Mel7c4UlihxNLieZjOA6Lz9JG5HxSQZQMZYV2A

Page: 1



Scale = 1:36.8

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	n/a	-	n/a	999	197/144
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.26	Vert(TL)	n/a	-	n/a	999	
TCDL	15.0	Rep Stress Incr	YES	WB	0.23	Horiz(TL)	0.00	5	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-SH							
BCDL	10.0										
										Weight: 49 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SPF 1650F 1.5E  
BOT CHORD 2x4 SPF 1650F 1.5E  
OTHERS 2x4 WW Stud/Std

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 1=19-7-8, 5=19-7-8, 6=19-7-8,  
7=19-7-8, 8=19-7-8  
Max Horiz 1=56 (LC 14)  
Max Uplift 1=-28 (LC 10), 5=-34 (LC 11),  
6=-136 (LC 15), 8=-136 (LC 14)  
Max Grav 1=319 (LC 20), 5=319 (LC 21),  
6=948 (LC 21), 7=369 (LC 1),  
8=948 (LC 20)

#### FORCES

(lb) - Maximum Compression/Maximum Tension

#### TOP CHORD

1-9=-125/30, 9-10=-53/38, 2-10=-30/105,  
2-3=-146/99, 3-4=-146/97, 4-11=-13/105,  
11-12=-30/14, 5-12=-125/7

#### BOT CHORD

1-8=-8/45, 7-8=-8/45, 6-7=-8/45, 5-6=-8/45

#### WEBS

3-7=-329/69, 2-8=-790/207, 4-6=-790/207

#### NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust)  
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat.  
II; Exp C; Enclosed; Hip Roof; Common Truss; MWFRS  
(envelope) exterior zone and C-C Exterior(2E) 0-11-5 to  
3-11-5, Interior (1) 3-11-5 to 9-10-8, Exterior(2R) 9-10-8  
to 13-10-8, Interior (1) 13-10-8 to 18-9-11 zone;  
cantilever left and right exposed; end vertical left and  
right exposed; C-C for members and forces & MWFRS  
for reactions shown; Lumber DOL=1.33 plate grip  
DOL=1.33

- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- 4) Unbalanced snow loads have been considered for this design.
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 4-0-0 oc.
- 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 8) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 28 lb uplift at joint 1, 34 lb uplift at joint 5, 136 lb uplift at joint 8 and 136 lb uplift at joint 6.
- 10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



REVIEWED FOR DESIGN CRITERIA ONLY  
October 8, 2020

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MITek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988707
2001565	V02	Valley	1	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 06004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MITek Industries, Inc. Wed Oct 07 16:51:48  
ID:snXfabMwge1Ak3hUbr97fsyWSaS-QT0Sa\_IdNNcYVrWZvS9oGbJHVNUB?Ys4g4izu7yV29

Page: 1



Scale = 1:32.8

Plate Offsets (X, Y): [3:0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.46	Vert(LL)	n/a	-	n/a	999	197/144
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.28	Vert(TL)	n/a	-	n/a	999	
TCDL	15.0	Rep Stress Incr	YES	WB	0.21	Horiz(TL)	0.00	5	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-SH							
BCDL	10.0										
										Weight: 37 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SPF 1650F 1.5E  
BOT CHORD 2x4 SPF 1650F 1.5E  
WEBS 2x4 WW Stud/Std

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (size) 1=15-7-8, 5=15-7-8, 6=15-7-8, 7=15-7-8  
Max Horiz 1=43 (LC 14)  
Max Uplift 1=22 (LC 10), 5=23 (LC 11), 6=112 (LC 15), 7=114 (LC 14)  
Max Grav 1=340 (LC 20), 5=340 (LC 21), 6=864 (LC 21), 7=864 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-8=-82/41, 8-9=-72/48, 9-10=-71/157, 2-3=-70/30, 3-4=-70/30, 4-10=-70/157, 10-11=-71/48, 5-11=-82/41  
BOT CHORD 1-7=-52/107, 6-7=-52/107, 5-6=-52/107  
WEBS 2-7=-715/229, 4-6=-715/229

#### NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust)  
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; Hip Roof; Common Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-11-5 to 3-11-5, Interior (1) 3-11-5 to 7-10-8, Exterior(2R) 7-10-8 to 12-1-7, Interior (1) 12-1-7 to 14-9-11 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33

- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- 4) Unbalanced snow loads have been considered for this design.
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 4-0-0 oc.
- 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 8) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 22 lb uplift at joint 1, 23 lb uplift at joint 5, 114 lb uplift at joint 7 and 112 lb uplift at joint 6.
- 10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



REVIEWED FOR  
DESIGN CRITERIA  
ONLY  
October 8, 2020

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MITek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Rosville, CA 95061




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988708
2001565	V03	Valley	1	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MITek Industries, Inc. Wed Oct 07 16:51:48  
ID:CTp72VDPVYWIHDmBuKyBAKyWSae-QT0Sa\_IdNNcYVWZvS9cGbJHjNTI7Za4g4Izu7yVI29

Page: 1



Scale = 1:25.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	In	(loc)	I/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.51	Vert(LL)	n/a	-	n/a	999	197/144
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.37	Vert(TL)	n/a	-	n/a	999	
TCDL	15.0	Rep Stress Incr	YES	WB	0.16	Horiz(TL)	0.00	3	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-SH							
BCDL	10.0										
										Weight: 26 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SPF 1650F 1.5E  
BOT CHORD 2x4 SPF 1650F 1.5E  
OTHERS 2x4 WW Stud/Std

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.  
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 1=11-7-8, 3=11-7-8, 4=11-7-8  
Max Horiz 1=-31 (LC 15)  
Max Uplift 1=-46 (LC 10), 3=-50 (LC 15), 4=-59 (LC 10)  
Max Grav 1=385 (LC 20), 3=385 (LC 21), 4=724 (LC 1)

#### FORCES

(lb) - Maximum Compression/Maximum Tension

#### TOP CHORD

1-5=-168/46, 5-6=-48/53, 2-6=-28/71, 2-7=-28/71, 7-8=-48/50, 3-8=-168/43

#### BOT CHORD

1-4=-1/46, 3-4=-1/46

#### WEBS

2-4=-519/223

#### NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; Hip Roof; Common Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-11-5 to 3-11-5, Interior (1) 3-11-5 to 5-10-8, Exterior(2R) 5-10-8 to 10-1-7, Interior (1) 10-1-7 to 10-9-11 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.

- 3) TCLL: ASCE 7-16; Pf=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- 4) Unbalanced snow loads have been considered for this design.
- 5) Gable requires continuous bottom chord bearing.
- 6) Gable studs spaced at 4-0-0 oc.
- 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 8) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 46 lb uplift at joint 1, 50 lb uplift at joint 3 and 59 lb uplift at joint 4.
- 10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



REVIEWED FOR DESIGN CRITERIA ONLY  
October 8, 2020



**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MI-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MITek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MITek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988709
2001565	V04	Valley	1	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:49  
ID:sW7E7n9GgQuaBSuDSnM0TGyWSaj-ufZqnKJG8hkP675mTAhtopFWXnpuk2JEvk2XQSyV28

Page: 1



Scale = 1:21.4

Plate Offsets (X, Y): [2:0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.25	Ver(LL)	n/a	-	n/a	999	197/144
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.31	Ver(TL)	n/a	-	n/a	999	
TCDL	15.0	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-P							
BCDL	10.0										
										Weight: 16 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SPF 1650F 1.5E

BOT CHORD 2x4 SPF 1650F 1.5E

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

#### REACTIONS

(size) 1=7-7-8, 3=7-7-8

Max Horiz 1=19 (LC 15)

Max Uplift 1=45 (LC 10), 3=45 (LC 11)

Max Grav 1=412 (LC 20), 3=412 (LC 21)

#### FORCES

(lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-545/324, 2-3=-545/324

BOT CHORD 1-3=-262/477

#### NOTES

1) Wind: ASCE 7-16; Vult=115mph (3-second gust)  
Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat.  
II; Exp C; Enclosed; Hip Roof; Common Truss; MWFRS  
(envelope) exterior zone and C-C Exterior(2E) zone;  
cantilever left and right exposed; end vertical left and  
right exposed; C-C for members and forces & MWFRS  
for reactions shown; Lumber DOL=1.33 plate grip  
DOL=1.33

2) Truss designed for wind loads in the plane of the truss  
only. For studs exposed to wind (normal to the face),  
see Standard Industry Gable End Details as applicable,  
or consult qualified building designer as per ANSI/TPI 1.

3) TCLL: ASCE 7-16; P=40.0 psf (Lum DOL=1.15 Plate  
DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0;  
Cs=1.00; Ct=1.10

4) Unbalanced snow loads have been considered for this  
design.

5) Gable requires continuous bottom chord bearing.

6) Gable studs spaced at 4-0-0 oc.

7) This truss has been designed for a 10.0 psf bottom  
chord live load nonconcurrent with any other live loads.

8) \* This truss has been designed for a live load of 40.0psf  
on the bottom chord in all areas where a rectangle  
3-06-00 tall by 2-00-00 wide will fit between the bottom  
chord and any other members.

9) Provide mechanical connection (by others) of truss to  
bearing plate capable of withstanding 45 lb uplift at joint  
1 and 45 lb uplift at joint 3.

10) This truss is designed in accordance with the 2018  
International Residential Code sections R502.11.1 and  
R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



REVIEWED FOR  
DESIGN CRITERIA  
ONLY

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITTEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Rosville, CA 95061




Job	Truss	Truss Type	Qty	Ply	YAVAPAI COUNTY 1 BDRM	R63988710
2001565	V05	Valley	1	1	Job Reference (optional)	

Western Truss & Components, Flagstaff, AZ - 86004,

Run: 8.33 S Jul 22 2020 Print: 8.330 S Jul 22 2020 MiTek Industries, Inc. Wed Oct 07 16:51:49  
ID:cnyq6i2dofsc3iU4OluclNyWSas-ufZqnKJG8hkP675mTAh1opFX4nllk2JEvk2XQSyVI28

Page: 1



Scale = 1:18.2

Plate Offsets (X, Y): [2:0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/dell	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.15	TC	0.15	Ver(L)	n/a	-	n/a	999	197/144
(Roof Snow = 40.0)		Lumber DOL	1.15	BC	0.00	Ver(TL)	n/a	-	n/a	999	
TCDL	15.0	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.01	3	n/a	n/a	
BCLL	0.0*	Code	IRC2018/TPI2014	Malrix-P							
BCDL	10.0										
										Weight: 4 lb	FT = 20%

#### LUMBER

TOP CHORD 2x4 SPF 1650F 1.5E

#### BRACING

TOP CHORD Structural wood sheathing directly applied or 3-9-0 oc purlins.

BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (size) 1=3-7-8, 3=3-7-8

Max Horiz 1=9 (LC 15)

Max Uplift 1=38 (LC 10), 3=38 (LC 11)

Max Grav 1=156 (LC 20), 3=156 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-2=-43/39, 2-3=-43/39

#### NOTES

- 1) Wind: ASCE 7-16; Vult=115mph (3-second gust) Vasd=91mph; TCDL=6.0psf; BCDL=6.0psf; h=33ft; Cat. II; Exp C; Enclosed; Hip Roof; Common Truss; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.33 plate grip DOL=1.33
- 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 3) TCLL: ASCE 7-16; P=40.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
- 4) Unbalanced snow loads have been considered for this design.
- 5) Gable requires continuous bottom chord bearing.
- 6) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
- 7) Gable studs spaced at 4-0-0 oc.

8) \* This truss has been designed for a live load of 40.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.

9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 38 lb uplift at joint 1 and 38 lb uplift at joint 3.

10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



REVIEWED FOR DESIGN CRITERIA ONLY  
October 8, 2020

**WARNING** - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSI/TPI Quality Criteria, DSB-85 and BCSI Building Component Safety Information available from Truss Plate Institute, 2870 Crain Highway, Suite 203 Waldorf, MD 20601





MiTek USA, Inc.  
400 Sunrise Avenue, Suite 270  
Roseville, CA 95661



## Symbols

### PLATE LOCATION AND ORIENTATION



This symbol indicates the required direction of slots in connector plates.

\* Plate location details available in MITek 20120 software or upon request.


### PLATE SIZE

4 X 4  
The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

### LATERAL BRACING LOCATION



### BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TPI1: National Design Specification for Metal Plate Connected Wood Truss Construction.

DSB-89: Design Standard for Bracing.


BCSI: Building Component Safety Information, Guide to Good Practice for Handling,

Installing & Bracing of Metal Plate

Connected Wood Trusses.

## Numbering System

6-4-8 dimensions shown in feet-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

### PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1968  
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3. These truss designs rely on lumber values established by others.

© 2012 MITek® All Rights Reserved



MITek Engineering Reference Sheet: Mill-7473 rev. 5/19/2020

## General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.

REVIEWED FOR DESIGN CRITERIA ONLY